



**NUMALIGARH REFINERY LIMITED**  
(A GOVERNMENT OF INDIA ENTERPRISE)  
NRL COMPLEX, NUMALIGARH,  
Dist : GOLAGHAT, ASSAM 785699  
Tel.: 03776-265413 Fax : 03776-265514



## **Schedule of Rate**

### **TENDER DOCUMENT**

### **FOR**

**Construction of Boundary Wall around NRL Police Outpost(2143)**

**Tender No. OC20000072**

### **PART - II : PRICED BID**

**PREPARED & ISSUED BY**  
**NUMALIGARH REFINERY LIMITED**  
( A Govt. of India Enterprise )

Item Ref.	Description	Unit	Qty	Rate in		Amount
				Figures	Words	

**00010 Construction of brick wall around Police.**

The item covers the following services:

10		Cubic meter	160.000		
	Earthwork in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. all kind of soil.				
20		Cubic meter	10.000		
	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering -all work upto plinth level. c) 1:4:8 ( 1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size )				
30		Cubic meter	40.000		
	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering and shuttering, finishing and reinforcement - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).				

Item Ref.	Description	Unit	Qty	Rate in		Amount
				Figures	Words	
40	Brickwork with bricks of class designation 75 in foundation and Plinth in a) cement work 1:4 ( 1 cement : 4 coarse sand )	Cubic meter	75.000			
50	Filling available excavated earth (excluding rock) in trenches , plinth , sides of foundation etc. in layers not exceeding 20 cm in depth: consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5m.	Cubic meter	120.000			
60	Reinforcement for RCC work including straightening, cutting , bending, placing in position and binding all complete. b) Cold twisted bars.	Kilogram	4,000.000			
70	Centring and shuttering including strutting, propping etc. and removal of form for foundations ,footings bases of columns etc. for mass concrete.	Square meter	55.000			

Item Ref.	Description	Unit	Qty	Rate in		Amount
				Figures	Words	
80	Centring and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams girders, bressumers and cantilevers.	Square meter	90.000			
90	Centring and shuttering including strutting, propping etc. and removal of form for Columns, pillars, piers, abutments, post and on struts.	Square meter	190.000			
100	12 mm cement plaster of mix 1:4 ( 1 cement : 4 coarse sand )	Square meter	300.000			
110	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 ( 1 cement : 4 coarse sand )	Square meter	300.000			
120		Kilogram	30.000			

Item Ref.	Description	Unit	Qty	Rate in		Amount
				Figures	Words	
130	Providing and fixing MS round holding down bolts with nuts and washer plates complete.  Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladders, railings, brackets, gates & similar works.	Kilogram	900.000			
140	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: two or more coats on new work.	Square meter	150.000			
150	Finishing walls with water proofing cement paint "Snowcem -Plus" of M/s Snocem India Ltd., or equivalent of required shade; New work (Two or more coats applied @ 3.84 kg/10 sqm).	Square meter	550.000			

Item Ref.	Description	Unit	Qty	Rate in		Amount
				Figures	Words	

**Total :**

Percentage rebate(if any) in words :

Percentage :

Less Rebate :

Grand Total in Words :

Grand Total :

Signature :

Name :

Address of the :

Contractor :

Place :

Date :